

### GLOBAL QA

Corpac's own skilled QA team inspects and oversees quality at every step. From mill through delivery, our skilled engineers, manufacturers and logistics experts work together to ensure integrity, compliance and timely delivery.

### TURNKEY SOLUTIONS

Our comprehensive inventory and global network of mills enable us to fulfill your requirements with immediate availability for a wide range of sizes and grades, as well as to provide global mill sourcing for specialized projects.

### SPECIAL SERVICES

We provide coatings, galvanizing, beveling, threading, slotting, cut-to-length, bends, quench and temper, fabrication, double-jointing and on-site assistance.

### CROSSOVER DISTRIBUTION MODEL

Corpac provides a range of services spanning the global supply chain by integrating the roles of manufacturers, trading companies, distributors and logistics providers.

### SUPPLY CONTRACTS

### JUST IN TIME PROGRAMS

We design these predetermined delivery schedules specifically for each customer, to meet product flow, while safeguarding on-site stock depletion and minimizing storage space and costs. Deliveries can be set to single, multiple or roving locations based on project needs.

 ISO 9001:2015 - ISO/TS 29001:2020  
Distribution Management System Certified



20803 Biscayne Blvd., Suite 502  
Aventura (Miami), Florida 33180  
sales@corpacsteel.com  
www.corpacsteel.com

Phone: +1 (888) 799-5869  
Phone: +1 (305) 918-0540  
Fax: +1 (305) 931-2251



### AVAILABLE STEEL GRADES INCLUDE API 2H GR. 50 AND API 2W GR. 50, AND SUPPLEMENTS

All our platform products are manufactured to meet customer requirements and under API 2B specifications with 100% X-rays of circumferential welds, 10% X-rays of longitudinal welds (Pipe Ends at 30° +/-2.5°), and a welding procedure qualified at -40°Celsius.

#### PROJECT KU S (API 2H)

|                             |             |           |
|-----------------------------|-------------|-----------|
| Bracing Pipes               | 101NT       | 92MT      |
| Bracing Pipe Outside Diam.  |             | 14" - 36" |
| Bracing Pipe Wall Thickness |             | 1" - 1.5" |
| Bracing Pipe Weight         | 297NT < 10" | >229NT    |
| Deck Legs                   | 240NT       | 318MT     |
| Deck Legs Outside Diameter  |             | 48" & 54" |
| Deck Legs Weight            |             | 218 MT    |
| Jacket Legs                 | 622NT       | 565MT     |
| Piles                       | 2,583NT     | 2,344MT   |

#### PROJECT ZAAP-B

|                             |             |           |
|-----------------------------|-------------|-----------|
| Bracing Pipes (API 2H)      | 140NT       | 127MT     |
| Bracing Pipe Outside Diam.  |             | 14" - 36" |
| Bracing Pipe Wall Thickness |             | 1" - 1.5" |
| Bracing Pipe Weight         | 297NT < 10" | >229NT    |
| Deck Legs                   | 246NT       | 223MT     |
| Deck Legs Outside Diameter  |             | 48" & 54" |
| Deck Legs Weight            |             | 223MT     |
| Jacket Legs                 | 763NT       | 692MT     |
| Piles                       | 2,733NT     | 2,480MT   |

#### PROJECT ZAAP-A

|                                |             |           |
|--------------------------------|-------------|-----------|
| Bracing Pipes (API 2H Gr50)    | 142NT       | 129MT     |
| Bracing Pipe Outside Diam.     |             | 14" - 36" |
| Bracing Pipe Wall Thickness    |             | 1" - 1.5" |
| Bracing Pipe Weight            | 297NT < 10" | >229NT    |
| Deck Legs (A36 & API 2H Gr 50) | 227NT       | 206MT     |
| Deck Legs Outside Diameter     |             | 48" & 60" |
| Deck Legs Weight               |             | 206 MT    |
| Jacket Legs                    | 943NT       | 856MT     |
| Piles                          | 2,615NT     | 2,373MT   |

#### PROJECT ZAAP-D

|                             |             |           |
|-----------------------------|-------------|-----------|
| Bracing Pipes (API 2H)      | 142NT       | 129MT     |
| Bracing Pipe Outside Diam.  |             | 14" - 36" |
| Bracing Pipe Wall Thickness |             | 1" - 1.5" |
| Bracing Pipe Weight         | 297NT < 10" | >229NT    |
| Deck Legs                   | 235NT       | 213MT     |
| Deck Legs Outside Diameter  |             | 48" & 60" |
| Deck Legs Weight            |             | 213 MT    |
| Jacket Legs                 | 962NT       | 873MT     |
| Piles                       | 2,615NT     | 2,373MT   |

We have the expertise and experience to help you execute your projects successfully. Please contact us today to discuss how we can collaborate with your offshore project plans.

